



SECTION

NOTES:

1. PREPARE ALL ROOF SURFACES AS REQUIRED BY THE FLUID APPLIED SYSTEM MANUFACTURER.
2. (IF RUST IS PRESENT) PRIME ENTIRE ROOF WITH "STABLERUST" PRIMER @ 200 SF/GAL. MIN. COVERAGE.
3. REMOVE LOOSE OR DAMAGED FASTENERS AND REPLACE WITH FASTENERS DESIGNED TO PENETRATE THE DECK AND SUPPORTING MEMBERS WITH NEOPRENE WASHERS AT THE SCREW HEAD.
4. DECK CONFIGURATIONS MAY DIFFER FROM THE DECK PROFILE INDICATED, BUT THE APPLICATION SHALL REMAIN THE SIMILAR.
5. PREMIUM COAT SYSTEM- FOUNDATION COAT, FABRIC, FOUNDATION COAT, AND FINISH COAT COMPONENTS. ALL FASTENERS ARE TREATED WITH HYDROCAPS AND FOUNDATION COAT. ALL VERTICAL SEAMS ARE TREATED WITH FOUNDATION COAT 4", 6", OR 8" FABRIC DEPENDING ON PROFILE OF THE ROOF. (CONTACT TECHNICAL DEPARTMENT) HORIZONTAL SEAMS ARE COVERED WITH 12" FABRIC AND FOUNDATION COAT.
6. FOUNDATION COAT- COMBINED COVERAGE (2 COATS) AT MINIMUM RATE OF 40 SF/GALLON.
7. FINISH COAT- COMBINED COVERAGE (2 COATS) AT MINIMUM RATE OF 70 SF/GALLON.
8. PRIMING- REFER TO HYDROSTOP SPECIFICATIONS FOR DECK PRIMING REQUIREMENTS.

**HYDRO
STOP**

PREMIUM COAT SYSTEM

SECTION AT PANEL SEAM
10 YEAR SYSTEM

DATE:

08/26/10

SHEET No :

MR-2-10